



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

September 24, 1964

RECEIVED
STATE CORPORATION COMMISSION

SEP 29 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Ken Stivers of Champlin Oil & Refining Co has this date requested permission to plug the following described well:

Mr. Stivers guarantees payment of the plugging fee.

Operator's full Name: Champlin Oil & Refining Company

Complete Address: P.O. Box 308, Ellinwood, Kansas

Lease Name: Richardson-Smith Well No. 1

Location: SE SE SE Sec. 6 Twp. 20 Rge. 8 (E) (W) X

County Rice Total Depth 3350' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Stivers was instructed to plug the well as follows:

Fill hole with mud to 200'. Push plug and 1/4 sack hulls to 200' and cement hole with 20 sacks through drill pipe.

Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,

Conservation Division Agent