



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

May 31, 1964 RECEIVED
STATE CORPORATION COMMISSION

JUN 3 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Richard Hogg of Isern Drilling Co. has this

date requested permission to plug the following described well:

Mr. Hogg guarantees payment of the plugging fee.

Operator's full Name: Ben C. W. Hyde, Jr.

Complete Address: 4722 Broadway, Kansas City, Missouri

Lease Name: Taylor Well No. 1

Location: C SE SE Sec. 16 Twp. 20 Rge. 8 (W) X

County Rice Total Depth 3504' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hogg was instructed to plug the well as follows:

Fill hole with mud to 210'. Push plug and 1/2 sack hulls

to 210' and cement hole with 25 sacks through drill pipe.

Fill hole with mud to 40'. Push plug and 1/2 sack hulls to

40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,


Conservation Division Agent