

State of Kansas



15.159.30243.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

February 28, 1966

RECEIVED  
STATE CORPORATION COMMISSION

MAR 2 1966

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bill Banks of Isern Drilling Company has this

date requested permission to plug the following described well:

Mr. Banks guarantees payment of the plugging fee.

Operator's full Name: Ben C. W. Hyde, Jr. and Isern-Wells

Complete Address: 4722 Broadway, Kansas City, Missouri 64112

Lease Name: Tobias "B" Well No. 2

Location: C W/2 NE Sec. 16 Twp. 20 Rge. 8 NE (W) X

County Rice Total Depth 3485' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Banks was instructed to plug the well as follows:

Fill hole with mud to 220'. Push plug and 1/4 sack hulls to 220' and  
cement hole with 20 sacks through drill pipe. Fill hole with mud to  
40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks  
cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,

Albert J. Loman  
Conservation Division Agent