

State of Kansas



15.159.30046.0000

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg.
 WICHITA, KANSAS 67202

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 10 1969
 CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

December 26, 1968

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Ed Schonoff of Pipe Pullers, Inc. has this date requested permission to plug the following described well:

Mr. Schonoff guarantees payment of the plugging fee.

Operator's full Name: Hyde-Isern-Wells

Complete Address: 4000 Somerset Drive, Prairie Village, Kansas 66208

Lease Name: Tobias "B" Well No. 1

Location: NW NW NE Sec. 16 Twp. 20 Rge. 8 (E) (W) X

County: Rice Total Depth 3489' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Schonoff was instructed to plug the well as follows:


Fill hole with sand to 3250' and cement with 3 sacks cement.

Fill hole with mud to 220'. Set rock bridge from 220' to 210' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Set

rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


 Conservation Division Agent