



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

May 15, 1964

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

MAY 19 1964

Dear Sir:

CONSERVATION DIVISION

Mr. Richard Hogg of Isern Drilling Company has this Wichita, Kansas

date requested permission to plug the following described well:

Mr. Hogg guarantees payment of the plugging fee.

Operator's full Name: Ben C. W. Hyde, Jr

Complete Address: 4722 Broadway, Kansas City 12, Missouri

Lease Name: Sentny Well No. 1

Location: C SE SW Sec. 16 Twp. 20 Rge. 8 (E) (W) X

County Rice Total Depth 3495' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Hogg was instructed to plug the well as follows:

Fill hole with mud to 215'. Push plug and 1/2 sack hulls  
to 215' and cement hole with 20' sacks through drill pipe.

Fill hole with mud to 40'. Push plug and 1/2 sack hulls  
to 40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,

Conservation Division Agent