



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

August 27, 1963

RECEIVED
STATE CORPORATION COMMISSION

SEP 3 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Robert Miller of Graves Drlg. Co., Inc. has this

date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company, Inc.

Complete Address: 1625 Wichita Plaza Bldg., Wichita, Kansas

Lease Name: Tobias Well No. 1

Location: CNW NE Sec. 24 Twp. 20 Rge. 8 (W) X

County Rice Total Depth 3572' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Miller was instructed to plug the well as follows:

Circulate heavy mud. Fill hole with mud to 200'. Push
plug and 1/4 sack hulls to 200' and cement with 20 sacks
through drill pipe. Fill hole with mud to 30'. Push
plug and 1/4 sack hulls to 30' and cap hole with 8 sacks
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

Conservation Division Agent