

State of Kansas



15.159.20071.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

October 18, 1967

RECEIVED
OCT 24 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bill Banks of Isern Drilling Co. has this
date requested permission to plug the following described well:

Mr. Banks guarantees payment of the plugging fee.

Operator's full Name: Isern-Wells and Associates

Complete Address: P.O. Box 486, Ellinwood, Kansas 67526

Lease Name: Nathan Bundy Well No. 1

Location: App. C SE SW Sec. 23 Twp. 20 Rge. 8 (W) X

County Rice Total Depth 3670' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Banks was instructed to plug the well as follows:

Fill hole with mud to 240'. Push plug and 1/4 sack hulls to 240' and

cement hole with 25 sacks through drill pipe. Fill hole with mud to

40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks

cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

William J. Lomax
Conservation Division Agent