

State of Kansas



15.159.30259.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

February 16, 1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. J. Paul Lacey of Beardmore Drilling Company has this date requested permission to plug the following described well:

Mr. Lacey guarantees payment of the plugging fee.

Operator's full Name: Beardmore Drilling Company, et al

Complete Address: 700 One-Twenty Bldg., Wichita, Kansas

Lease Name: Sleeper Well No. 1

Location: C NE NW Sec. 29 Twp. 20 Rge. 8 (E) (W) X

County Rice Total Depth 3665' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lacey was instructed to plug the well as follows:

Fill hole with mud to 210'. Push plyg and 1/4 sack hulls to 210' and

cement hole with 25 sacks through drill pipe. Fill hole with mud to

40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks

cement.

FEB 23 1966

Bridge rathole, and cement with 2 sacks.

CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,

Conservation Division Agent