

State of Kansas



15.159.05030.0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission
CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. MAIN
WICHITA, KANSAS 67202
RECEIVED
STATE CORPORATION COMMISSION
MAR 22 1967
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

March 10, 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. D. B. Pulley of Forbes Casing Pulling, Inc. has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Forbes Casing Pulling, Inc.

Complete Address: P.O. Box 221, Great Bend, Kansas

Lease Name: Massey Well No. 1

Location: C SW SE Sec. 28 Twp. 20 Rge. 8 (E) (W) X

County Rice Total Depth 3360' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pulley was instructed to plug the well as follows:

Fill hole with sand to 3250' and cement with 5 sacks.

Fill hole with mud to 205'. Set rock bridge from 205' to 195' and

cement hole with 20 sacks. Fill hole with mud to 40'. Set rock bridge

from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent