

State of Kansas



15.159.05024.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

February 25, 1967
CORPORATION COMMISSION

MAR 7 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. D. B. Pulley of Forbes Casing Pulling, Inc. has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Thomas A. Allan

Complete Address: R. R. #1, Great Bend, Kansas

Lease Name: Florence Edgar Well No. 1

Location: SE NE SW Sec. 27 Twp. 20 Rge. 8 (E)(W) X

County Rice Total Depth 3303' Oil Well EX

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Pulley was instructed to plug the well as follows:

Fill hole with sand to 3280' and cement with 5 sacks.

Fill hole with mud to 200'. Set rock bridge from 200' to 190' and

cement hole with 20 sacks cement. Fill hole with mud to 40'. Set

rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent