

State of Kansas



15.159.05027.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
AUG 30 1966
STATE CORPORATION COMMISSION

AUG 1 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. John Jones of Southwest Casing Pulling, Inc. has this date requested permission to plug the following described well:

Mr. Jones guarantees payment of the plugging fee.

Operator's full Name: Thomas H. Allan

Complete Address: Route 1, Great Bend, Kansas

Lease Name: Will Edgar Well No. 2

Location: C N/2 S/2 SW Sec. 27 Twp. 20 Rge. 8 (E) (W) X

County Rice Total Depth 3316' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Jones was instructed to plug the well as follows:

Fill hole with sand to 3280' and cement with 5 sacks.

Fill hole with mud to 200'. Set rock bridge from 200' to 190' and

cement hole with 20 sacks. Fill hole with mud to 40'. Set rock bridge

from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent