


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

RICE County. Sec. 26 Twp. 20S Rge. 10W (#77) (W)

Location as "NE/CNW/SW" or footage from lines SW NE SE  
Lease Owner PETROLEUM, INC.  
Lease Name LOESCH Well No. 1  
Office Address ROUTE 2, GREAT BEND, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed MAY 3, 19 62  
Application for plugging filed MAY 3, 19 62  
Application for plugging approved MAY 3, 19 62  
Plugging commenced MAY 3, 19 62  
Plugging completed MAY 3, 19 62  
Reason for abandonment of well or producing formation No PRODUCIBLE ZONES



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production NONE 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well CECIL JONES  
Producing formation --- Depth to top --- Bottom --- Total Depth of Well 3405 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	256'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set:

MUDDED UP WITH HEAVY MUD TO 240' FOLLOWED BY WOODEN PLUG AND 1/4 SACK HULLS. PLACED 25 SACKS CEMENT THROUGH DRILL PIPE ONTO HULLS.  
MUDDED UP WITH HEAVY MUD TO 35' FOLLOWED BY WOODEN PLUG, 1/4 SACK HULLS AND 8 SACKS CEMENT TO BASE OF WELL CELLAR. 2 SACKS CEMENT IN RAT HOLE.

RECEIVED  
STATE CORPORATION COMMISSION

5-23-62 MAY 23 1962

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING COMPANY  
Address ROUTE 2, GREAT BEND, KANSAS

STATE OF KANSAS COUNTY OF BARTON, ss.  
DON SEARLE (employee of owner) or ~~known to operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. DON SEARLE, DIST. PROD. SUPT.

(Signature) Don Searle  
ROUTE 2, GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 21ST day of MAY, 19 62

My commission expires APRIL 14, 1963. Arthur J. Miles Notary Public.

# WELL LOG

15.159.02895.0000

COMPANY PETROLEUM, INCORPORATED

SEC. 26 T. 20S R. 10W

FARM LOESCH NO. 1


LOC. SW, NE, SE

TOTAL DEPTH 3405'

COUNTY RICE CO., KANSAS

COMM. April 25, 1962 COMP. May 3, 1962

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8-5/8" @ 256' w/200 sax.

ELEVATION 1755' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

85	Clay & sand
150	Shale
256	Red bed
387	Red bed & shale
405	Anhydrite
1230	Shale & shells
1530	Lime
1625	Lime & shale
1755	Shale & lime
2160	Lime & shale
2355	Shale & lime
2570	Lime & shale
2655	Lime
2800	Lime & shale
2875	Lime
3010	Shale & lime
3305	Lime
3338	Conglomerate
3362	Lime & sand
3386	Lime & shale
3405	Lime
3405	T. D.

**RECEIVED**  
STATE CORPORATION COMMISSION

MAY 23 1962

CONSERVATION DIVISION  
Wichita, Kansas

State of KANSAS  
County of BARTON } SS

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state the above and foregoing is a true and correct copy of the log of the #1 LOESCH well.

Subscribed and sworn to before me this 18th day of May 1962

My Commission Expires: April 14, 1963

*Verne A. Morris*

*Arthur J. Miles*  
NOTARY PUBLIC