

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Rice County, Sec. 34 Twp. 20 Rge. 10 (E) (W)
SW NW NW

Location as "NE/CNW/SW" or footage from lines
Schreiner Petroleum Company
Lease Owner
Lease Name Groves Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 1/10/67 19
Plugging completed 1/18/67 19
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3363 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	290	none
				5 1/2	3125	2421

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Raised mast, checked hole to 3100', sanded to 3050' and ran 5 sacks of cement. Cleaned cellar, rigged up on 5 1/2" casing, worked pipe to 23" tension at 20 points. Checked hole, shot pipe at 2608 & 2512', parted pipe, pulled 22 joints of 5 1/2" casing. Cleared floor, loaded rack, lowered mast and racked unit. Raised mast, rigged up floor, ran overshot on 22 joints of 5 1/2" casing. Checked hole, had bridge at 1600', could not work pipe loose, pumped two loads of water. Checked hole, had bridge at 1628', spotted 20 barrels of oil. Shot pipe at 2391', pulled 85 joints. Bailed hole to 285', set rock bridge and ran 20 sacks of cement. Mudded hole to 40', rock bridge and ran 10 sacks of cement. Racked unit and tallied pipe.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JAN 24 1967
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
CHASE, KANSAS

SUBSCRIBED AND SWORN TO before me this 20 day of Jan, 1967

My commission expires Oct 22-1970
Notary Public.

November 31, 1965

DRILLERS LOG

Re: Groves #1
SW NW NW Section 34-20S-10W
Rice County, Kansas

COMPANY: Schreiner Petroleum
CONTRACTOR: B & B Drilling Inc.
TOTAL DEPTH: 3361'
COMMENCED: November 15, 1965
COMPLETED: November 23, 1965

0	302	Surface Hole
280	320	Cement
320	880	Red Bed & Shale
880	1480	Shale & Lime
1480	1819	Shale & Lime
1819	2320	Shale & Lime
2320	2785	Shale & Lime
2785	2930	Lime & Shale
2930	2955	Lime & Shale
2955	2990	Lime
2990	3072	Lime
3072	3125	Lime
3125	3210	Lime
3210	3265	Lime
3265	3315	Lime & Shale
3315	3359	Lime & Shale
3359	3361	Lime
3361	3363	Total Depth Ran 5 1/2" casing

RECEIVED
STATE CORPORATION COMMISSION

JAN 11 1967

CONSERVATION DIVISION
Wichita, Kansas

We certify the above and foregoing to be true and correct copy of the log on the #1 Groves, located in Rice County, Kansas

B & B DRILLING INC.

Bill Laker President

Anna A. Nuss Notary Public
Subscribed and sworn to before me this
5th day of January, 1967, My commission
expires May 31, 1970