

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Rice

County. Sec. 30 Twp. 20 Rge. 10 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW NE NW

Lease Owner B & R Drilling, Inc.

Lease Name Yeo Well No. 1

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed January 10, 1949 19

Application for plugging filed March 23, 1951 19

Application for plugging approved March 23, 1951 19

Plugging commenced March 24, 1951 19

Plugging completed March 30, 1951 19

Reason for abandonment of well or producing formation All Oil Recovered

If a producing well is abandoned, date of last production March 7, 1951 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Depth to top Bottom Total Depth of Well 3304' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	135'	None
				5 1/2"	3302'	2516'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging Record.

Plugged back with sand to 3290', dumped 4 sax of cement with dump bailer, top of cement 3262', filled with mud to 3080'. Dumped 4 sax of cement with dump bailer, top of cement 3055'. Mudded hole to 135', set rock bridge at 135', dumped 15 sax cement. Top of cement 90'. Mudded Hole to 15', dumped 5 sax cement fro cap.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to B & R Drilling, Inc.
Address Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
W. A. Michaelis, Jr. (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. A. Michaelis, Jr.

Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 13th day of April, 19 51

My commission expires 6-17-54

Notary Public.

28-5091-s 8-50-10M

PLUGGING
FILE SEC 30T 20R 10W
BOOK PAGE 69 LINE 23

APR 17 1951
CONSERVATION DIVISION

4-17-51

