

WELL PLUGGING RECORD


STATE OF KANSAS STATE CORPORATION COMMISSION

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bittling Building Wichita, Kansas

Rice County, Sec. 29 Twp. 20 Rge. 10 (W)



Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NW 1/4 NW 1/4 SE 1/4 Lease Owner DERBY OIL COMPANY ET AL Lease Name Yeo Well No. / Office Address Wichita, Kansas Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole Date well completed March 19 19 44 Application for plugging filed March 20 19 44 Application for plugging approved March 23 19 44 Plugging commenced March 20 19 44 Plugging completed March 20 19 44 Reason for abandonment of well or producing formation Not Productive

Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Ruel Durkee Producing formation None Depth to top Bottom Total Depth of Well 3355 Feet Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: 8 5/8, 225, None.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3355' to 225' Mud 225' to 210' Rock Bridge - and Cement 210' to 26' Mud 26' to 6' Rock and Cement 6' to Surface - dirt



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Derby Oil Company Address Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick S. E. Banks (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S.E. Banks Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 27th day of March 1944

My commission expires July 31, 1947

Notary Public signature

Record of Well No. #1

Farm: Yes

Location: NW SE

Sec. 29 Twp. 20 Rge. 10W

Contractor: Crow Drlg. Co.

County: Rice

Drilling Comm.: 3-6-44

State: Kansas

Elevation: 1732

Drilling Comp.: 3-19-44

CASING RECORD

size feet kind weight

8 5/8 225' 125 sax bulk cement by Halliburton

| Formation | Bottom |
|----------------------|--------|
| Sand & Gravel | 0- 42' |
| Shale & Shells | - 140 |
| Red Rock | - 195 |
| Red Rock & Shale | - 225 |
| Red Rock | - 385 |
| Anhydrite | - 410 |
| Red Shale & Shells | - 685 |
| Shale & Shells | - 806 |
| Salt & Shale Streaks | - 978 |
| Salt | -1052 |
| Salt & Shale | -1090 |
| Shale & Shells | -1200 |
| Lime | -1252 |
| Anhydrite & Shale | -1302 |
| Anhydrite | -1348 |
| Shale & Lime | -1622 |
| Shale | -1643 |
| Bro. Lime | -1692 |
| Bro. Lime & Shale | -1772 |
| Lime | -1892 |
| Lime & Shale | -1909 |
| Lime & Shale Streaks | -2010 |
| Shale & Lime | -2395 |
| Shale | -2459 |
| Lime | -2480 |
| Lime & Shale | -2513 |
| Shale | -2555 |
| Lime | -2727 |
| Bro. Lime | -2777 |
| Lime | -2879 |
| Lime & Shale | -2920 |
| Shale & Lime Streaks | -2970 |
| Lime & Shale | -3012 |
| Lime | -3292 |
| Shale | -3304 |
| Lime | -3318 |
| Dolomite | -3355 |

GEOLOGICAL SURVEY

Tops:

| | |
|-----------|-------|
| Brn. Lime | 2965' |
| Lansing | 2989' |
| Simpson | 3264' |
| Arbuckle | 3303' |

Total Depth 3355'

No shows, Plug and abandoned.

2965
1732
-1233

PLUGGING
FILE # 29 20 RLOK
BOOK PAGE 11 LINE 32

STATE OF KANSAS
COMMISSIONER
MAR 28 1944
CHAS. STARNES
ENGINEER