



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

WICHITA, KANSAS 67202

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 24 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

January 15, 1969

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

1-24-69

Dear Sir:

Mr. D. B. Pulley of Forbes Casing Pulling, Inc. has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company, Inc.

Complete Address: 410 Fourth Nat'l Bank Bldg., Wichita, Kansas 67202

Lease Name: Evans Well No. 1

Location: CE/2 NW NE Sec. 33 Twp. 20 Rge. 8 (E) (W) X

County: Rice Total Depth 3357' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Pulley was instructed to plug the well as follows:

Fill hole with sand to 3225' and cement with 5 sacks cement.

Fill hole with mud to 220'. Set rock bridge from 220' to 210' and cement

hole with 25 sacks cement. Fill hole with mud to 40'. Set rock bridge

from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

  
 Conservation Division Agent