

State of Kansas



15.159.05034.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 20 1966

December 2, 1966

CONSERVATION DIVISION
Wichita, Kansas

12-20-66

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. D. B. Pulley of Forbes Casing Pulling, Inc. has this
date requested permission to plug the following described well:

Mr. Pully guarantees payment of the plugging fee.

Operator's full Name: Thomas A. Allan

Complete Address: R. R. #1, Great Bend, Kansas

Lease Name: Shaffer Well No. 1

Location: C E/2 NE NW Sec. 33 Twp. 20 Rge. 8 (E) (W) X

County Rice Total Depth 3310' Oil Well

Gas Well X Input Well SWD Well D & A Lost Hole

Mr. Pulley was instructed to plug the well as follows:

Fill hole with sand to 3265' and cement with 5 sacks.

Fill hole with mud to 185'. Set rock bridge from 185' to 175' and

cement hole with 20 sacks. Fill hole with mud to 40'. Set rock

bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent