

RECEIVED
STATE CORPORATION COMMISSION

FEB 24 1964

2-24-64

FORM - CP-2
Rev. 6-26-62

State of Kansas



CONSERVATION DIVISION
Wichita, Kansas

15.009.05237.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Neven H. Veail of Neven H. Veail has this
date requested permission to plug the following described well:

Mr. Neven H. Veail guarantees payment of the plugging fee.

Operator's full Name: Neven H. Veail

Complete Address: 1401 McKinley, Great Bend, Kansas

Lease Name: Hood Well No. # 1

Location: SE SE SE Sec. 10 Twp. 20 Rge. 12 (E) (W) W

County Barton Total Depth 3408 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Neven H. Veail was instructed to plug the well as follows:

8 5/8" 210' Cwc.

Filled hole with heavy mud to 200'; set plug with 1/4
sax hulls; displaced 25 sax cement thru drill pipe. Mud
to 40'; 1/2 sax hulls; plug & displaced 12' sax cement,
cementing to base of cellar.

Very truly yours,

Don [Signature]
WELL Plugging Supervisor