



15.159.30184.0000

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL Chairman
ALVIN P. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

6-16-65
RECEIVED
STATE CORPORATION COMMISSION
JUN 16 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Earl Morgan of Mast Drilling, Inc. has this
date requested permission to plug the following described well:

Mr. Morgan guarantees payment of the plugging fee.

Operator's full Name: Robin Supply Corporation

Complete Address: 1322 East 50th St., Tulsa, Oklahoma

Lease Name: Bohrer Well No. 1

Location: SE SW NW Sec. 3 Twp. 20 Rge. 9 ~~W~~ (W) X

County Rice Total Depth 3298' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Morgan was instructed to plug the well as follows:

Fill hole with mud to 220'. Push plug and $\frac{1}{2}$ sack hulls to
220' and cement hole with 25 sacks through drill pipe.

Fill hole with mud to 40'. Push plug and $\frac{1}{2}$ sack hulls to
40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,

Conservation Division Agent