



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

July 22, 1981

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Bill Woodrow of Aspen Oil, Inc. has this

date requested permission to plug the following described well:

Operator's Full Name: Aspen Oil, Inc.

Complete Address: 7701 E. Kellogg, Suite 575, Wichita, Kansas 67207

Lease Name: ~~Aspen~~ Canzoneri Well No. 1-A

Location: C SE Sec. 36 Twp. 20 Rge. 8 (E) (W)

County: Rice Total Depth: 3356'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D&A X

Other well as hereafter indicated:       

Mr. Woodrow was instructed to plug the well as follows:

8-5/8"-201'-175 sacks Circulate and fill hole with mud. Pump 50 sacks  
cement through drill pipe at 300'. Fill hole with mud to 40'. Push plug  
and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Cement rathole  
with 10 sacks cement. Cement mouse hole with 10 sacks cement.

7-23-81

Very truly yours,

Albert J. Loman  
Conservation Division Agent  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

JUL 23 1981

CONSERVATION DIVISION  
Wichita, Kansas