

State of Kansas



JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

March 17, 1964

3-19-64  
**RECEIVED**  
STATE CORPORATION COMMISSION

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

MAR 19 1964

CONSERVATION DIVISION  
Wichita, Kansas

Dear Sir:

Mr. Duke Burt of Burt Drilling Company has this  
date requested permission to plug the following described well:

Mr. Burt guarantees payment of the plugging fee.

Operator's full Name: American Oil & Gas Company

Complete Address: 809 Bitting Bldg., Wichita, Kansas

Lease Name: Malone Well No. 1

Location: NE SE SW Sec. 25 Twp. 20 Rge. 10 (E) (W) X

County Rice Total Depth 3375' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Burt was instructed to plug the well as follows:

Fill hole with mud to 200'. Push plug and 1/2 sack hulls  
to 200' and cement hole with 25 sacks through drill pipe.

Fill hole with mud to 40'. Push plug and 1/2 sack hulls to  
40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,