



15.159.20854.0000

JOHN CARLIN
R. C. LOUX
JANE T. ROY
WILLIAM G. GRAY
Carol J. Larson, Executive Secretary

Governor
Chairman
Commissioner
Commissioner

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

April 24, 1980

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Bruck
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Jac Brannum of Emphasis Oil Operations has this date requested permission to plug the following described well:

Mr. Brannum guarantees payment of the plugging fee.

Operator's full Name: Berne Fairchild Oil, Inc.

Complete Address: 207 Lochinvar, Wichita, Kansas

Lease Name: Malone Well No. 1

Location: SW SW SW Sec. 25 Twp. 20 Rge. 10 (W)

County: Rice Total Depth 3368' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Brannum was instructed to plug the well as follows:

8 5/8" - 250' - con. circ. Fill hole with mud. Pump 40 Sacks
Cement through drill pipe at 450'. Pump 25 Sacks
Cement through drill pipe at 240'. Push plug and 1/2
Sack hulls to 40' and cap hole with 10 Sacks cement.
Bridge rathole and cement with 10 Sacks

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours,

APR 29 1980

CONSERVATION DIVISION
Wichita, Kansas

[Signature]
Conservation Division Agent