



15.159.19431.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

June 18, 1965

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. R. E. Smith of Glenn & Smith Pipe Pulling has this
date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Muir-Thompson, Inc.

Complete Address: 201 Garlinghouse Bldg., Topeka, Kansas

Lease Name: Proffitt "C" Well No. 1

Location: NW NW NW Sec. 24 Twp. 20 Rge. 10 (E) (W) X

County Rice Total Depth 2460' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Smith was instructed to plug the well as follows:

Push 4 1/2" plug to 2335'. Fill hole with sand to 2325' and
cement with 3 sacks. Fill hole with mud to 195'. Set rock
bridge from 195' to 185' and cement hole with 20 sacks.
Fill hole with mud to 40'. Set rock bridge from 40' to 30'
and cap hole with 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours,

JUN 25 1965

CONSERVATION DIVISION
Wichita, Kansas

Robert J. Loman
Conservation Division Agent