

State of Kansas



FORM CP-2

15.159.21158.0000

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

May 19, 1981

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Harold Williams of Banner Drilling, Inc. has this
date requested permission to plug the following described well:

Operator's Full Name: Clarion Resources, Inc.

Complete Address: 1625 Broadway # 1800, Denver, Colorado

Lease Name: Loesch Well No. 1-26

Location: SW NW SW Sec. 26 Twp. 20 Rge. 10 XX (W)

County: Rice Total Depth: 3460'

Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☒ X

Other well as hereafter indicated:

Mr. Williams was instructed to plug the well as follows:

8-5/8"-228'-200 sacks. Fill hole with mud. Pump 50 sacks 50-50 pozmix
through drill pipe at 375' (top of Anhydrite). Fill hole with mud to
40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement.

No rathole-no mousehole.

RECEIVED
STATE CORPORATION COMMISSION
5-22-81
MAY 22 1981

Very truly yours,

CONSERVATION DIVISION
Wichita, Kansas

[Signature]
Conservation Division Agent