

State of Kansas



15.159.30243.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

JAN 26 1967

CONSERVATION DIVISION
Wichita, Kansas

1-26-67

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

January 10, 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co. has this
date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Schreiner Petroleum Company

Complete Address: 501 Petroleum Bldg., Wichita, Kansas

Lease Name: Grove Well No. 1

Location: SW NW NW Sec. 34 Twp. 20 Rge. 10 (E) (W) X

County Rice Total Depth 3363' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:


Fill hole with sand to 3050' and cement with 5 sacks.

Fill hole with mud to 285'. Set rock bridge from 285' to 275' and

cement hole with 20 sacks. Fill hole with mud to 40'. Set rock bridge

from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


Conservation Division Agent