



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

October 22, 1963

RECEIVED
STATE CORPORATION COMMISSION

OCT 25 1963

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Frank Pfannensteil of Garvey Drilling Co. has this

date requested permission to plug the following described well:

Mr. Pfannensteil guarantees payment of the plugging fee.

Operator's full Name: High Plains Production Co. & Oil & Gas Futures Inc.

Complete Address: 300 Insurance Bldg., Wichita, Kansas

Lease Name: Burns Well No. 1

Location: SW NW NE Sec. 34 Twp. 20 Rge. 10 (S) (W) X

County Rice Total Depth 3363' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pfannensteil was instructed to plug the well as follows:

Circulate heavy mud. Fill hole with mud to 250'. Push
plug and 1/4 sack hulls to 250' and cement hole with 20 sacks
through drill pipe. Fill hole with mud to 35'. Push plug
and 1/4 sack hulls to 35' and cap hole with 10 sacks cement.
Bridge rathole, and cement with 2 sacks.

Very truly yours,

Conservation Division Agent