



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 25 1971

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Crowe of Garvey Drlg. has this

date requested permission to plug the following described well:

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Tenneco Oil Co.

Complete Address: 2000 Classen Center East Oklahoma City, Okla.

Lease Name: L. J. Franklin Well No. 1-35

Location: C/ E/2 SE NE Sec. 35 Twp. 20 Rge. (E)(W) 16

County: Pawnee Total Depth 3962' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Crowe was instructed to plug the well as follows:

 Gun pits, circulate heavy mud, set cementing plug at 600' and displace

 40 sk cmt thru drill pipe. Heavy mud to 250' set cementing plug and

 displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing

 plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

 Leo F. Massey
Conservation Division Agent