

90  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

JUL 10 1964

CONSERVATION DIVISION  
Wichita, Kansas

7-10-1964

Operator's Full Name Ben C. W. Hyde, Jr.

Complete Address: 4722 Broadway, Kansas City, Missouri

Lease Name Taylor Well No. 2

Location SE SW SE Sec. 16 Twp. 20 Rge. 8 (E) (W) X

County Rice Total Depth 3500'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Isern Drilling Company

Address: Box 486, Ellinwood, Kansas License No.     

Operation Completed: Hour 9:30 PM Day 6 Month July Year 1964

The Above well was plugged as follows:

Hole filled with mud to 215'. Plug and 1/2 sack hulls pushed to 215'  
and hole cemented with 20 sacks through drill pipe. Hole filled with  
mud to 40'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to  
base of cellar with 10 sacks. Rathole bridged, and cemented with 2  
sacks.

INVOLICED

I hereby certify that the above well was plugged as herein stated.

DATE 7/10/64  
INV. NO. 9446-u

Signed: [Signature]  
Well Plugging Supervisor