

JP
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAR 22 1965

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Independent Lease Management Co.

Complete Address: R. R. #4, Hutchinson, Kansas

Lease Name Tobias Well No. 1

Location SE SW NW Sec. 22 Twp. 20 Rge. 8 (E) (W) X

County Rice Total Depth 3466'

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 10 AM Day 17 Month March Year 1965

The Above well, was plugged as follows:

4 1/2" plug pushed to 3250'. Hole filled with sand to 3240' and hole
cemented with 3 sacks. Hole filled with mud to 190'. Rock bridge set
from 190' to 180' and hole cemented with 20 sacks. Hole filled with
mud to 40'. Rock bridge set from 40' to 30' and hole cemented to base
of cellar with 10 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *[Signature]*
Well Plugging Supervisor

DATE 3/22/65

INV. NO. 848-W