

15.159.05030.0000 R

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAR 22 1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Forbes Casing Pulling, Inc.

Complete Address: P.O. Box 221, Great Bend, Kansas

Lease Name Massey Well No. 1

Location C SW SE Sec. 28 Twp. 20 Rge. 8 (E) (W) X

County Rice Total Depth 3360'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Operator

Address: License No. 49

Operation Completed: Hour 4PM Day 18 Month March Year 1967

The Above well was plugged as follows:
Hole filled with sand to 3250' and cemented with 5 sacks. Hole filled with mud to
205'. Rock bridge set from 205' to 195' and hole cemented with 20 sacks. Hole filled
with mud to 40'. Rock bridge set from 40' to 30' and hole cemented to base of cellar
with 10 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 3/22/67

INV. NO. 4941-W