

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Rice County, Sec. 16 Twp. 20S Rge. (E) 8 (W)

Location as "NE/CNW/SW" or footage from lines NW NW NE
Lease Owner Ben C. W. Hyde, Jr.
Lease Name Tobias "B" Well No. 1
Office Address 4000 Somerset Drive, Prairie Village, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed June 1 19 65
Application for plugging filed December 11 19 68
Application for plugging approved 19
Plugging commenced December 29 19 68
Plugging completed January 7 19 69
Reason for abandonment of well or producing formation depleted



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3480 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	222'	8 5/8"	222'	none
		0	3488'	4 1/2"	3488'	2410.55

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed plug to 3275', set 10' sand bridge and dumped 3 sacks of cement.

Pushed plug to 220', set 10' rock bridge and dumped 25 sacks of cement.
Filled hole with mud to 30' and capped hole with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 17 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Pipe Pullers, Inc.
Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Evelyn Roth (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas
(Address)

W E L L L O G

HYDE ISERN WELLS, TOBIAS "B" #1
 NW NW NE, Section 16-20S-8W
 Rice County, Kansas

Figures indicate bottom of formation:

ELEVATION: 1657' KB

PIPE RECORD:

8 5/8" set @ 222'
 with 225 sacks.
 4 1/2" set @ 3488'
 with 125 sacks.

ROTARY COMMENCED: 5-24-65
 ROTARY COMPLETED: 6-1 -65

TOPS

Heebner	2722
Brown Lime	2861
Lansing	2899
Kinderhook Lime	3353
Kinderhook Sand	3439
Maquoketa	3465

0 to 10	cellar
	20 clay
	70 sand
	825 shale
	1050 salt
	1430 shale & shells
	1580 lime & shale
	2425 shale & shells
	3439 lime & shale
	3445 sand
	3480 shale

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 12 1968
 CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
 COUNTY OF BARTON) ss

I, Dean Wells, Partner of Isern Drilling Company, contractor for the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts and statements and matter herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

Dean Wells

 Dean Wells, Partner

Subscribed and sworn to before me on this 3rd day of June, 1965.

George A. Meyer

 George A. Meyer, Notary Public

My commission expires Feb 10, 1967.