

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rice County, Sec. 24 Twp. 20S Rge. (X) 8 (W)

Location as "NE/CNW/SW" or footage from lines C NW NE

Lease Owner Mull Drilling Co., Inc.

Lease Name Tobias Well No. 1

Office Address 1625 Wichita Plaza, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed August 27, 1963

Application for plugging filed August 27, 1963

Application for plugging approved August 27, 1963


Plugging commenced August 27, 1963

Plugging completed August 27, 1963

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert J. Toman, Holyrood, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3572 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 200 feet. Followed by wooden plug and 1/4 sack hulls. Placed 20 sacks cement onto hulls. Mudded up with heavy mud to 30 feet followed by wooden plug and 8 sacks cement to base of well cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

SEP 6 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.

Address Box 332, El Dorado, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss.

John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves

Box 332, El Dorado, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 30th day of August, 1963

My commission expires April 30, 1967

Betty Brandt

Notary Public.



R O T A R Y D R I L L E R S ' L O G

OPERATOR: Muml Drilling Co., Inc. DRILLING COMMENCED: August 20, 1963
1625 Wichita Plaza
Wichita, Kansas

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: August 27, 1963
Box 332
El Dorado, Kansas

CASING RECORD: 209' - 8-5/8" surface cemented with 175 sacks cement.
LOCATION: Tobias No. 1
C NW NE
Section 24-20S-8W
Rice County, Kansas

0 - 70	Sand
70 - 208	Shale
208 - 945	Shale, clay and red bed
945 - 1735	Shale & lime
1735 - 2130	Shale & shells
2130 - 2411	Shale & lime
2411 - 2575	Lime & shale
2575 - 3175	Lime
3175 - 3247	Lime & shale
3247 - 3263	Shale & lime
3263 - 3303	Conglomerate
3303 - 3405	Shale & lime
3405 - 3433	Shale
3433 - 3545	Lime
3545 - 3560	Miesner
3560 - 3572	Viola
3572	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION
SEP 6 1963
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John Graves
President

STATE OF KANSAS)
) SS
BUTLER COUNTY)

Subscribed and sworn to before me, a Notary Public, this 30th day of August, 1963.

My commission expires:
April 30, 1967

Betty Brandt
Betty Brandt Notary Public