


WELL PLUGGING RECORD

Give All Information  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Rice County, Sec. 23 Twp. 20S Rge. 8W (EX) (W)  
Location as "NE/CNW/SW" or footage from lines Approx C SE NW  
Lease Owner ISERN-WELLS & ASSOCIATES  
Lease Name Verlan Bundy Well No. 1  
Office Address BOX 486, Ellinwood, Kansas 67526  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed December 15 19 67  
Application for plugging filed December 15 19 67  
Application for plugging approved December 15 19 67  
Plugging commenced December 15 19 67  
Plugging completed December 15 19 67  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3600 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Shale		195	251	8 5/8"	248'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with mud to 240' plug 1/4 sack hulls, 25 sacks cement.  
Filled hole with mud to 40' plug, 1/2 sack hulls, 10 sacks cement.  
Two sacks cement in Rat Hole.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Isern Drilling Company  
Address Box 486, Ellinwood, Kansas 67526

STATE OF KANSAS, COUNTY OF BARTON, ss.  
Dean Wells (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Wells  
Box 486, Ellinwood, Kansas 67526  
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of December, 1967.

My commission expires February 10, 1971.  
George A. Meyer Notary Public.

W E L L L O G

ISERN-WELLS & ASSOCIATES,  
 VERLAN BUNDY #1, Approx C SE NW  
 Section 23-20S-8W, Rice Co., Kansas

ELEVATION: 1646' GL  
 1648' DF  
 1650' KB

Figures indicate bottom of formation:

0	to	65	sand
		180	red rock
		251	shale
		1300	shale & shells
		1675	lime & shale
		2400	shale & shells
		2645	lime & shale
		2840	shale & lime
		3430	Lime & shale
		3530	lime, shale & sand
		3580	lime
		3600	lime & shale
		3600	Rotary Total Depth
			Dry and Abandoned.

PIPE RECORD:  
 8 5/8" set at 248' with  
 250 sacks cement.

ROTARY COMMENCED: 12-8 -67  
 ROTARY COMPLETED: 12-16-67

TOPS:

Heebner	2700	
Brown Lime	2840	
Lansing	2875	
Conglomerate Chert	3270	
Kinderhook Lime	3357	
Kinderhook Sand	3418	
Viola	3456	
Simpson Sand	3505	Arbuckle 3568
STATE OF KANSAS )	ss	
COUNTY OF BARTON )		

RECEIVED  
 DEC 20 1967  
 STATE OF KANSAS

I, W. F. Banks, Drilling Superintendent of Isern Drilling Company, contractor for the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matter herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

*W. F. Banks*  
 \_\_\_\_\_  
 W. F. Banks

Subscribed and sworn to before me on this 18th day of December, 1967.

*George A. Meyer*  
 \_\_\_\_\_  
 George A. Meyer, Notary Public

My commission expires: 2-10-71.

C  
O  
P  
Y