

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Request to:
Conservation Division
State Corporation Commission
211 N. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rice County, Sec. 22 Twp. 20 Rge. 8 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE SW NW
Lease Owner Independent Lease Management Company
Lease Name Tobias Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 3-13-65 19____
Plugging completed 3-16-65 19____
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3467 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	189'	None
				4-1/2"	3466'	1952'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3467', pushed plug to 3250', sanded to 3240' and dumped 3 sacks of cement @ 3240' with dump bailer. Pulled 4 1/2" casing, checked fluid to 190', set rock bridge to 180' and dumped 20 sacks of cement @ 180'. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

MAR 29 1965 3-29-65

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or ~~(owner or operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of March, 1965

My commission expires May 20, 1968
Milton J. Volin Notary Public.

15.159.00379.0000

BRINRICH DRILLING CO.
WICHITA, KANSAS

Well: Tobias # 1

Commenced RD 5-16-55
Completed RD 5-25-55

Total Depth: 3466'

Casing: 189' 8 5/8" O.D. 28 1/2# 8 rn thd.
3466' 4 1/2" O.D. 125 # of cement

SE SW NW
Sec. 22-20-8
Rice County

Elevation: 1652

Contractor: Brinrich
Drilling Co.

11# SS

STRATA	DEPTH	TOPS
Surface soil	9	
Sand	100	
Shale	145	
Red Bed & Shale	193	
Red Bed	194	
Anhydrite	206	
Red Bed & Shale	455	
Shale & shells	585	
Salt & shale	954	
Broken Lime	1030	
Lime	1840	
Broken Lime	1872	
Shale & Lime	2040	
Lime & Shale	2575	
Lime, shale & chert	3263	
Lime & shale	3355	
Lime, shale & chert	3395	
Total Depth	3466	
		Brown Lime 2835-1183
		Lansing 2874-1222
		Sooy Cong. 3250-1598
		Sooy Chert 3261-1609
		Viola 3389-1737
		Simpson 3396-1744
		Arbuckle 3459-1807
		Total Depth 3466

RECEIVED
STATE CORPORATION COMMISSION

FEB 18 1955

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

BRINRICH DRILLING COMPANY, INC.
BY

Ralph B. McLaughlin
Ralph B. McLaughlin (Sec-Treas.)

Signed and sworn to in my presence this 2nd day of June, 1955, by Ralph B. McLaughlin, Secretary-Treasurer of the Brinrich Drilling Company, Inc., a corporation in the State of Kansas.

Donna S. Riley
Notary Public

My commission expires December 31, 1958.