

WELL PLUGGING RECORD **REC'D MAY 6 1957**

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rice County, Sec. 22 Twp. 20S Rge. 8W (E) (W)

T 20S NORTH R 8W

		22	
*			

Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines SE NW SW
 Lease Owner Brunson Production & Exploration Co.
 Lease Name Morris Well No. 1
 Office Address 333 First Nat'l. Bank - Wichita, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Gas Well
 Date well completed September 21 19 55
 Application for plugging filed April 6 19 57
 Application for plugging approved _____ 19 _____
 Plugging commenced April 4 19 57
 Plugging completed April 6 19 57
 Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production _____ 19 _____
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
 Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3449 Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	195'	None
				5-1/2"	3449'	2838'
				T. D. inside pipe 3419'. Casing perforated from 3269' to 3303'.		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled the hole with sand from 3419' to 3250' and ran 6 sacks of cement. Mudded the hole to 190', set a 10' rock bridge and ran 15 sacks of cement. Mudded the hole to 20', set a 5' rock bridge and ran 5 sacks of cement on top. Plugging completed.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.
 Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
I, Ralph B. McLaughlin (employee of owner) or OWNER/OPERATOR of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph B. McLaughlin
 (Address) _____

SUBSCRIBED AND SWORN TO before me this 6th day of May, 19 57

My commission expires March 6, 1961

Wanda Lou Bruce
 Wanda Lou Bruce Notary Public.

RECEIVED
 STATE CORPORATION COMMISSION

PLUGGING
 FILE SEC. 22 T. 20 R. 8W
 BOOK PAGE 4 LINE 29

MAY 7 - 1957

CONSERVATION DIVISION
 Wichita, Kansas

West Supply
Inch

15.159.05021.0000

BRINRICH DRILLING CO.

Well: Morris #1

SE-1/4 SW
22-20-8

Commenced R.D. -9-9-55
Completed R.D. 9-21-55

Rice County

Total Depth: 3449'

Elevation: 1653 BS

Casing: 195' 8 1/2" O.D. 25#
3449' 5 1/2" O.D. 14#

Contractor: Brinrich

100 feet
1000 feet

STRATA	DEPTH		TOPS
Surface sand & soil	40	Brown Lime	2844-1191
Sand	160	Lansing	2882-1229
Sand & shale	180	Sooy	3265-1612
Anhydrite	210		
Shale & Red Bed	400		
Shale & Shells	700		
Salt & Shale	920		
Shale & Shells	945		
Broken Lime	1150		
Lime & shale	1720		
Shale & Lime	1955		
Lime	3022		
Lime, Chirt Streaks	3189		
Lime	3250		
Lime & Shale	3265		
Conglomerate	3300		
Shale, Chirt & Lime	3326		
Lime, Shale & Sand	3382		
Sand, Shale & Chirt	3395		
Lime & Shale	3431		
Total Depth	3449		

93 photos
from 3303' to 3269'
by Lane Wells

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling report.

BRINRICH DRILLING COMPANY, INC.
BY

Ralph B. McLaughlin
Ralph B. McLaughlin - Sec. Treas.

Signed and sworn to in my presence this 25th day of September, 1955, by R. B. McLaughlin, Secretary of the Brinrich Drilling Company, Inc., a Corporation in the State of Kansas.

Donna L. Riley
Notary Public - Donna L. Riley

My commission expires December 31, 1958.

PLUGGING
FILE SEC. 22 T. 20 R. 9W
BOOK PAGE 4 LINE 29