

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rice County, Sec. 22 Twp. 20 Rge. 8 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NW NW SW'


Lease Owner Templeton Energy, Inc.
Lease Name KS14-1 WRIGHT Well No. 1 Houston
Office Address 850 The Main Bldg., 1212 Main St. TX
Character of Well (Completed as Oil, Gas or Dry Hole) 77002
Dry Hole

Date Well completed 9/25, 1981
Application for plugging filed 9/25, 1981
Application for plugging approved 9/25, 1981
Plugging commenced 9/25, 1981
Plugging completed 9/25, 1981
Reason for abandonment of well or producing formation
Dry Hole

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz
Producing formation Depth to top Bottom Total Depth of Well 4055'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	262'	8-5/8"	262'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from feet to
feet for each plug set.

120 sks 50/50 poz., 2% gel, 3% cc.,
60 sks @ 500'
40 sks @ 260'
10 sks & solid plug @ 40'
10 sks in rathole
Plug down 8:15 AM, 9/25/81
By Howco

RECEIVED
STATE CORPORATION COMMISSION

OCT 13 1981

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Allen Drilling Company

STATE OF KANSAS COUNTY OF BARTON
Gary Christopher (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Gary Christopher
P.O. Box 1389, Great Bend, KS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of October, 1981



My commission expires

Ruth Brack
Notary Public.

DRILLER'S WELL LOG

DATE COMMENCED: 9/16/81
DATE COMPLETED: 9/25/81

Templeton Energy, Inc.
KS14-1 WRIGHT No. 1 - NW NW SW
Sec. 22, Twp. 20S, Rge 8W,
Rice County, Kansas

ELEVATION: 1648' G.L.
1653' K.B.

FORMATION DATA:

2694 - 2833' Shale
2833 - 2873' Lime, shale
2873 - 3182' Lime
3182 - 3381' Shale, lime, chert, sand
3381 - 3390' Sand
3390 - 4006' Dolomite
4006 - 4055' Sand
4055' RTD

Heebner 2694'
B. Lime 2833'
Lansing 2873'
Conglomerate 3182'
Simpson Sand 3381'
Arbuckle 3390'
Reagan 4006'
RTD 4055'

SURFACE DATA:

Ran 6 jts new 20# 8-5/8"
casing; tally: 255'
Set @ 262' w/250 sks 50/50
poz., 2% gel, 3% cc. cement.
circulated; plug down 8:30 PM,
9/16/81, by Howco

PLUGGING DATA:

120 sks 50/50 poz., 2% gel,
3% cc: 60 sks @ 500'
40 sks @ 260'
10 sks & solid plug
@ 40'
10 sks in rathole
Plug down 8:15 AM, 9/25/81
By Howco; J.H.Metz, plugger

A F F I D A V I T

STATE OF KANSAS }
COUNTY OF BARTON } ss.

RECEIVED
STATE CORPORATION COMMISSION

OCT 13 1981

CONSERVATION DIVISION
STATE OF KANSAS

Gary Christopher, of lawful age, does swear and state that the
facts and statements herein contained are true and correct to the best
of his knowledge.

Gary Christopher

Subscribed and Sworn to before me this 7th day of October, 1981.

 RUTH BRACK
State of Kansas
Appt. Exp. 9/2/84

Ruth Brack
Notary Public

INVOICE
DATE 11-2-81
INV. NO. 8237-W