


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rice County, Sec. 29 Twp. 20 Rge. 8 (E) (W)



Locate well correctly on above Section Plat

Location as "NE/CNW/SE/SW" or footage from lines NE NW
Lease Owner Beardmore Drilling Company
Lease Name Sleeper Well No. 1
Office Address 700 - One Twenty Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2-17 19 66
Application for plugging filed 2-17 19 66
Application for plugging approved 2-17 19 66
Plugging commenced 2-17 19 66
Plugging completed 2-17 19 66
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3665 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface clay & sand		0	90'			
Shale & red beds		90'	221'	8-5/8	221	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

- 0 to 40' - 10 sacks cement
- 40' - wood plug
- 40' to 135' - heavy mud
- 135' to 210' - 25 sacks cement
- 210' - wood plug
- 210' to 3665' - heavy mud

RECEIVED
STATE CORPORATION COMMISSION
FEB 28 1966
CONSERVATION DIVISION
Wichita, Kansas

Also: 2 sacks cement in rat hole.

2-28-66

Name of Plugging Contractor Gabbert-Jones, Inc.
Address 514 Orpheum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. Heber Beardmore

(employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Heber Beardmore
700 - One Twenty Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 25th day of February, 19 66

My commission expires 7-13-67

Shirley Ann Jackson
Shirley Ann Jackson
Notary Public.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

RECEIVED
STATE CONSERVATION COMMISSION
FEB 28 1966
CONSERVATION DIVISION
Wichita, Kansas

SLEEPER #1
C NE NW SECTION 29-20S-8W
RICE COUNTY, KANSAS

COMMENCED: FEBRUARY 9, 1966
COMPLETED: FEBRUARY 17, 1966

OPERATOR - BEARDMORE DRILLING COMPANY

DEPTH		FORMATION	REMARKS
FROM	TO		
0	90	SURFACE CLAY AND SAND	
90	221	SHALE AND RED BED	RAN 11 JOINTS OF 8-5/8" CASING, SET @ 221' w/200 SACKS CEMENT.
221	250	RED BED	
250	1240	SHALE AND SHELLS	
1240	2155	LIME AND SHALE	
2155	2340	SHALE AND SHELLS	
2340	2950	LIME AND SHALE	
2950	3410	LIME	
3410	3530	LIME AND SHALE	
3530	3665	LIME	
3665	TD		DRY AND ABANDONED.

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C NE NW SECTION 29-20S-8W, RICE COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 22ND DAY OF FEBRUARY, 1966 PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
BARBARA J. LAYTON, NOTARY PUBLIC

MY COMMISSION EXPIRES FEBRUARY 1, 1968.