

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging of formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Rice County. Sec. 28 Twp. 20S Rge. 8W (E) (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. 330' from S Line, 990' W line.

Lease Owner. Sam Schneider

Lease Name. Massey #1 Well No. 1

Office Address. Hutchinson, Kansas

Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole

Date, well completed. March 11 1938

Application for plugging filed. March 13 1938

Application for plugging approved. March 13 1938

Plugging Commenced. 1938

Plugging Completed. March 22 1938

Reason for abandonment of well or producing formation. dry

If a producing well is abandoned, date of last production. - - - - - 1938

Was permission obtained from the Conservation Division or its agents before plugging was commenced?

yes

Name of Conservation Agent who supervised plugging of this well. Guy Wershing, Lyons, Kansas

Producing formation. Depth to top. Bottom. Total Depth of Well.


Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Run in	Pulled Out
	cemented	100 sacks		12 1/2	Surface	138'
				7"OD	3365'	2480'
				5-5/16	3460'	3460'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging from bottom to 160', heavy mud laden fluid wooden plug, 10 sacks cement, clay to 15', wooden plug, 7 sacks cement.



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. The Gerband-Pulse Oil & Drlg Co  
Address. 301 Hoke Building  
Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss. Clyde Pulse (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clyde Pulse

(Address)

SUBSCRIBED AND SWORN to before me this 25 day of March, 1938

Signature of Notary Public

My commission expires Feb. 8, 1939

Notary Public



15 159 05 031 0000

THE GERBRAND-PULSE OIL & DRILLING CO.  
301 HOKE BUILDING, HUTCHINSON, KANS.

MARCH 22, 1938

LOCATION: 330' from S line, 990' from W line, Sec. 28, Twp. 20S, Rge 8W, Rice County, Ks.

MASSEY #1

COMPANY: Sam Schneider, Gerbrand-Pulse Oil & Drilg. Co., Hutchinson, Kansas.

COMMENCED: February 7, 1938 - - - - - March 11, 1938, as a dry hole

Surface	0 to 28'	Top of K. C.	2918
Coarse Sand	68	Lime	3104
Blue Shale and Shells	153	Shale	3112
Cemented 12 1/2" (100 sacks)	131	Lime	3129
Shale and shells (show salt @ 860)	580	Shale	3124
Blue Shale & Lime Shells	1010	Lime	3200
Broken Lime	1205	Shale	3235
Chalky White Lime	1245	Shale and Lime	3255
Broken Lime	1335	Chert and Lime	3270
Lime and Shells	1560	Shale and Broken Lime	3280
Lime	1594	Conglomerate	3317
Broken Lime	1650	Shale and Lime	3343
Lime & Shale	1975	Shale and Shells	3368
Lime	2025	Conglomerate (show of oil)	3375
Broken Lime	2100	Sand	3390
Shale	2200	Dolomite	3399
Lime	2280	Vido Lime	3408
Broken Lime	2390	Simpson Sand	3450
Sandy Shale	2403	Green Shale	3476
Lime	2655	Siliceous Lime (H.F.U.)	3483
Shale	2675	CASING RECORDS	
Lime	2745	1 1/2" Surface 138', cemented 100 sacks	
Broken Lime	2810	7" OD Casing 3365'	
Shale	2877	5-3/16 3460'	
Lime	2883	Plugging from bottom to 160', heavy mud laden fluid, wood plug, 10 sacks cement, clay to 15', wooden plug 7 sacks cement.	
Shale	2900		

PLUGGING  
FILE NO. 22 20 R 8W  
BOOK PAGE 11 LINE 12

I, Clyde Pulse Manager of The Gerbrand-Pulse Oil & Drilg. Co, do hereby certify that this is a true and correct log of the formation encountered on the above mentioned well as taken from the daily drilling reports thereof.

Subscribed and sworn to before me this 22 day of Mar 1938

*Sam Schneider*  
Notary Public

Signed *Clyde Pulse*  
Manager