

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-159-21, P56

SE, Sec. 16, T 20 S, R 8 W

2310 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Tobias Well # 1

Operator: Raymond Oil Company, Inc.  
Name & Address One Main Place, Ste. 900  
Wichita, Kansas 67202

County Rice

Well Total Depth 3461 feet 112.48

Conductor Pipe: Size        feet

Surface Casing: Size 8 1/4 feet 281-180 sacks 2.25

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D&A X

Other well as hereinafter indicated       

Plugging Contractor Duke Drilling Company, Inc License Number 5929

Address P.O. Box 823, Great Bend, Kansas 67530

Company to plug at: Hour: 12:30 A Day: 12 Month: July Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Leonard Williamson

(company name) Duke Drilling Company, Inc (phone) 316-793-7859 unit 7107

were: Fill hole with heavy mud. Pump 50 sacks 50/50 Pozmix w/2%  
gel through drill pipe @ 340'. Fill hole with heavy mud to 40'.  
Push plug and 1/2 sack hulls to 40' and cap hole with 2  
Sacks Cement. Cement ratihole with 10 Sacks Cement.

Signed Stallard J. Loman  
(TECHNICIAN)

Plugging Operations attended by Agent?: All        Part        None X

Operations Completed: Hour: 2:05 A Day: 12 Month: July Year: 1984

ACTUAL PLUGGING REPORT Hole Filled with heavy mud. 50 Sacks 50/50 Pozmix  
with 2% gel pumped through drill pipe @ 340'. Hole Filled  
with mud to 40'. Plug and 1/2 sack hulls pushed to 40'  
and hole cemented to base of celler with 10 Sacks 50/50 Poz.  
Rathole cemented with 10 Sacks Pozmix

Remarks: Elev. 1649 Gb. TD in Kinderhook (no arbuacle)  
Halliburton Co. Ticket # 944010

I hereby certify that the above plugging instructions were given as herein stated  
and that I (~~did~~ / did not) observe this plugging.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 17 1984 Signed Stallard J. Loman  
(TECHNICIAN)

CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
Rev. 9-82  
mu

INVOICED

DATE 7-24-84

INV. NO. 2623