

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-04920-00-00  
Spot: CNWSENE Sec/Twnshp/Rge: 21-20S-12W  
3630 feet from S Section Line, 990 feet from E Section Line  
Lease/Unit Name: HULMBE Well Number: 6  
County: BARTON Total Vertical Depth: 3480 feet

Operator License No.: 3273  
Op Name: LOEB, HERMAN L.  
Address: PO BOX 524  
LAWRENCEVILLE, IL 62439

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 8.625 feet: 257  
Production: Size 5.5 feet: 3479  
Liner: Size \_\_\_\_\_ feet:

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/12/2002 10:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D.S. & W. WELL SERVICING, INC.  
Proposal Recvd. from: VERNON PFLUGHOEFT Company: D.S. & W. WELL SERVICING, INC. Phone: (620) 793-2440

Proposed Plugging Method: Emergency plug with rig over the hole.  
Junk in the hole.

Plugging Proposal Received By: JAY PFEIFER Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/13/2002 10:00 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

09-11-2002 - Drilled out of the pipe at 630'. Decided to P&A.  
09-12-2002 - TIH with tubing to 620'.  
Mixed and pumped 225 sxs 60/40 pozmix - 10% gel with 500# hulls.  
POOH and shut in for 3 hours.  
TIH with tubing to 620'.  
Mixed and pumped 150 sxs common with 3% CaCl.  
POOH. SIPN.  
09-13-2002 - TIH with tubing to 150' and circulated cement with 25 common with 3% CaCl.  
Hooked onto 8 5/8" and pumped 25 sxs cement.  
S.I.P. 200#.

RECEIVED  
SEP 18 2002 9-18-02  
KCC WICHITA

Remarks: SERVICE ACID, L.I.C.

Plugged through: TBO

District: 04

Signed Jay Pfeifer  
(TECHNICIAN)