

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

11-6 API NUMBER: 15-159-21,043-0000

C SE SE, SECTION 2 TOWNSHIP 20 RANGE 9W

OPERATOR LICENSE # 5585 660 FEET FROM S SECTION LINE
OPERATOR CLINTON PRODUCTION INC. 660 FEET FROM E SECTION LINE
NAME & 330 NORTH ARMOUR
ADDRESS WICHITA, KS 67206
LEASE NAME: FATHER FLANAGAN "A" #1
COUNTY: RICE
WELL TOTAL DEPTH: 3402' P/S 3374'
PIPE: 5 1/2" @ 2490'
SURFACE CASING: 8 5/8" @ 246'

110.56

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE
ADDRESS: P.O. BOX 209, CHASE, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 12:00 DAY: 6 MONTH: 11 YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: MANNY
COMPANY NAME: MIKE'S TESTING & SALVAGE PHONE: (316) 938-2943
WERE: SAND TO 2840' AND 5 SACKS

35 SACKS AT 1150'
35 SACKS AT 750'
300'- 0'

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 22 1996

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI CONSERVATION DIVISION
WICHITA, KS

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL PART NONE

COMPLETED: HOUR: 4:00PM DAY: 6 MONTH: 11 YEAR: 1996

ACTUAL PLUGGING REPORT: SANDED BOTTOM TO 2840' AND 5 SACKS OF COMMON. SHOT 5 1/2" CASING OFF AT 2414'. PULLED TO 1150', PUMPED 35 SACKS. PULLED TO 750', PUMPED 35 SACKS. PULLED TO 300', CIRCULATED CEMENT TO SURFACE.

REMARKS: 60/40 POZ 4% GEL ALLIED #1198

INVOICED

DATE 11-22-96
INV. NO. 47039

I DID OBSERVE THIS PLUGGING.
Jack Luthi
JACK LUTHI