

8-21

2-070726

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-159-21,160-0000

NE NE NW, SECTION 2 TOWNSHIP 20 RANGE 10W

OPERATOR LICENSE # 5895 4950 FEET FROM S SECTION LINE
OPERATOR GABLE OIL COMPANY 2970 FEET FROM E SECTION LINE
NAME & BOX 444
ADDRESS CHASE, KS 67524

LEASE NAME: SIEKER #1
COUNTY: RICE 108.55
WELL TOTAL DEPTH: 3340'
PIPE: 5 1/2" @ 3339'
SURFACE CASING: 8 5/8" @ 207'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A
OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE
ADDRESS: CHASE, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 9:30 DAY: 21 MONTH: 8 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: JAMES

COMPANY NAME: MIKE'S TESTING & SALVAGE PHONE: (316) 938-2943

WERE: SAND TO 2977' AND 5 SACKS
35 SACKS AT 1300'
35 SACKS AT 900'
260' TO SURFACE

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 12:00 DAY: 21 MONTH: 8 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED BOTTOM TO 2977' AND 5 SACKS OF COMMON. SHOT 5 1/2"
CASING OFF AT 2279'. PULLED TO 1300' AND PUMPED 35 SACKS. PULLED TO 900'
AND 35 SACKS. PULLED TO 260' AND CIRCULATED CEMENT TO SURFACE.

REMARKS: 60/40 POZ 4% GEL

RECEIVED
ALLIED WISAS CORPORATION COMMISSION
WICHITA, KS

SEP 11 1997

I DID OBSERVE THIS PLUGGING OPERATION DIVISION
WICHITA, KS
Jack Luthi
JACK LUTHI

INVOICED

DATE 9-11-97
INV. NO. 48964