

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-159-21044.0001

TECHNICIAN'S PLUGGING REPORT

Operator License # 5895

Operator: Gable Oil Company
Name &
Address Box 166
Chase, Kansas 67524

80' N 1/4 NW 1/4, Sec. 2, T 20 S, R 10 W 1/2

250' feet from N/S section line

990' feet from W/E section line

Lease Name Sicker Well # 2

County Rice

Well Total Depth 3345 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 266

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050 Rig #548

Address Box 176, Chase, Kansas 67524

Company to plug at: Hour: 11:00 AM Day: 16 Month: December Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO Norman Voth

(company name) Kelso Casing Pulling (phone) 316 938 2457

were: Fill hole with sand to 2990' and cement with 5 sacks
Cement. Squeeze hole with 5 sacks hulls, 25 sacks gel-
mud, and 100 sacks 50/50 Pozmix w/2% gel and 3% C.C.
Pump into 8 5/8" surface casing.

Signed Valley Loma
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3:00 PM Day: 17 Month: December Year: 1982

ACTUAL PLUGGING REPORT Pumped 5 sacks hulls and 7 sacks gel (see below).
Wash hole down to 500'. Pumped 6 sacks gel through tubing
at 500'. Circulated hole from 312' to cellar with 100 sacks
Cement circulated through tubing

Remarks: Had pumped 5 sacks Hulls and 7 sacks gel - blew hole
in surface casing about 4' down.
2684' of casing recovered

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / ~~did not~~) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION

JAN 07 1983

CONSERVATION DIVISION
Wichita, Kansas

Signed Valley Loma
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICED

DATE 1-12-83

INV. NO. 2083-u