

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-159-21,552.0000
 , Sec. 25, T 20S, R 10 W/E
1980 feet from 3/4S section line
990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5122

Lease Name Malone "B" Well # 1-25

Operator: Woodman-Iannitti Drilling Co.
Name & 1008 Douglas Building
Address Wichita, Kansas 67202

County Rice

Well Total Depth 3390 feet \$110.18

Conductor Pipe: Size feet

Surface Casing: Size 8 1/8 feet 210

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Operator & Sun Oilwell Cementing License Number 5122
Ric # 25

Address

Company to plug at: Hour: 1:00 PM Day: 4 Month: February Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Rich Wheeler

(company name) Woodman-Iannitti Drilling Co. (phone) 316 792-2921

were: Fill hole with heavy mud. Pump 50 sacks 50/50 Pozmix
w/2% gel through drill pipe at 310'. Fill hole with mud to 40'
Push plug and 1/2 sack hulls to 40' and cap hole with
10 sacks cement. Cement rat hole with 10 sacks cement.

Signed Alfred J. Loman
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:45 PM Day: 4 Month: February Year: 1983

ACTUAL PLUGGING REPORT

Same as above.

RECEIVED
STATE CORPORATION COMMISSION
FEB 24 1983
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Ticket # 14171 (Sun Oilwell Cementing)

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

Signed Alfred J. Loman
(TECHNICIAN)

INVOICED
MAR 25 1983

DATE
INV. NO. 3690-W