

5 020299

15.159.30213.0000

276R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 3-24-66

C/SR SW, SEC. 5, T. 20 S, R. 8 W
660 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5023

Lease Name Koons Well # 1

Operator: Kansas Petroleum

County Rice 108.45

Name & Address 225 N. Market, Ste. 310

Well Total Depth 3337 feet

Wichita, Kansas 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 7/8 feet 213

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, Kansas 67530

Company to plug at: Hour: 9:00 AM Day: 17 Month: July Year: 1986

Plugging proposal received from Randy Wagner

(company name) Great Bend Casing Pulling (phone) 316 793 9711

were: Fill hole with sand to 3250' and cement with 5 sacks.

Squeeze hole with 5 sacks hulls, 10 sacks Bentonite, and 125 sacks 60/40 Pozmix w/6% gel.

Plugging Proposal Received by Marian Hornech
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 AM Day: 17 Month: July Year: 1986

ACTUAL PLUGGING REPORT Hole Filled with sand to 3250 and cemented with 5 sacks cement. Hole squeezed with 4 sacks hulls, 10 sacks Bentonite, and 125 sacks 60/40 Pozmix w/6% gel.

5 1/2" - 3330-755s Perfs 3300-3337 Max Pressure 800 PSIG. Close in 250 PSIG

Remarks: 1200' of 5 1/2" casing recovered. Howco Ticket # 506445-5
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-7-86

AUG 5 1986

Signed Marian Hornech
(TECHNICIAN)

INV. NO. 14650

8-5-86