

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

K

API Number 15-159-21,187.0000

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Aspen Oil, Inc.

Complete Address 7701 E. Kellogg, Suite 575, Wichita, Kansas 67207

Lease Name ~~Osage~~ Canzoneri Well No. 1-A

Location C SE Sec. 36 Twp. 20 Rge. 8 (East) (West)

County Rice Total Depth 3356'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Co. Tools and Halliburton Co.

Address _____ License No. _____

Operation Completed: Hour: 11:30 PM Day: 22 Month: July Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows: 8-5/8"-201'-175 sacks

Hole circulated and filled with mud. 50 sacks 50-50 pozmix w/4% gel
and 3% cal. chl. pumped through drill pipe at 300'. Hole filled with
mud to 40'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to
base of cellar with 10 sacks cement. Rathole cemented with 10 sacks
cement. Mousehole cemented with 10 sacks cement.

7-23-81

RECEIVED
STATE CORPORATION COMMISSION

Jul 25 1981

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Conservation Division Agent

DATE 8-25-81

INV. NO. 6181-W