

15.159.03167.0001

2-070837

7-28

D-22,338 FEE FUND - 15-159-73201

990074-002

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER: Fee Fund Well

C NR NW NW, SECTION 29 TOWNSHIP 20S RANGE 10W  
OPERATOR LICENSE # 100 4950 FEET FROM S SECTION LINE  
OPERATOR Kansas Corporation Com. 4620 FEET FROM E SECTION LINE  
NAME & 130 S. Market # 2125  
ADDRESS Wichita, Ks. 67202

LEASE NAME: Yeo Peters # 2  
COUNTY: Rice  
WELL TOTAL DEPTH: 3555  
PIPE: 5 1/2" - 3350  
SURFACE CASING: 8" - 217

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD XX D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Mike's Testing & Salvage  
ADDRESS: P O box 647, Chase, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 8:00 A.M. DAY: 28th MONTH: July YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM: Mike Kelso

COMPANY NAME: Mike's Testing & Salvage PHONE: 316-938-2537

WERE: Perforate casing @ 1245'-850' & 270'

50 sacks on bottom  
35 sacks 850'  
270'- to 0'

PLUGGING PROPOSAL RECEIVED BY: Jack Luthi, KCC

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( XX ) PART ( \_\_\_\_\_ ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: \_\_\_\_\_ DAY: 28th MONTH: July YEAR: 1999

ACTUAL PLUGGING REPORT: Hit first bridge at 90' could not get thru. Called Kansas Fishing Tool Co. out with swivel and wash over pipe. Circulated hole to 842'. Got circulation. Wash down to 1245'. Pulled wash over pipe and went back in with tubing and bit. Got to 1250' and could get no further. Log Tech perforated casing at 1245'-850' & 270'. Ran tubing in to 1245', Pumped 30 sacks gel and 500 lbs. of hulls. Got circulation. Pumped 50 sacks. Pulled to 850', pumped 50 sacks with 4% CC. Pulled to 270' and let cement set for one (1) hour. Then circulated cement from 278' to surface. Also circulated on back side

REMARKS: Allied # 2637 60/40 4%

I DID OBSERVE THIS PLUGGING  
Jack Luthi  
Jack Luthi

FORM CP-2/3  
REV. 3/90

(R)