

1050123

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145 20.447.0000

NE NE NW, Sec. 35, T 20 S, R 16 W/E

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5042

Lease Name Bradley Well # 1

Operator: E. K. Edmiston
Name & 818 East 10th
Address Great Bend, KS 67530

County Pawnee

Well Total Depth 3788 feet 123.11

Production
~~XXXXXX~~ Pipe: Size 4 1/2 feet 3788

Surface Casing: Size 8 5/8 feet 1021

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: Noon Day: 25 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Mike Gomez

(company name) Kelso Casing Pulling (phone) 316-938-2416

were: 1st plug sand bottom back to 3700' and dump 4 sx cement on sand through bailer. 2nd plug pump through head in sequence 3 sx hulls, 10 sx gel, 75 sx cement, 15 sx gel, 1 sack hulls and release 8 5/8" plug and pump another 125 sx cement.

Signed Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 1 :10 pm Day: 25 Month: January Year: 19 84

ACTUAL PLUGGING REPORT 1st plug sand bottom back to 3700' and dump 4 sx cement on sand through bailer. 2nd plug pump through head in sequence 3 sx hulls, 10 sx gel, 75 sx cement, 15 sx gel, 1 sack hulls and release 8 5/8" plug and pump another 125 sx cement.

Remarks They recovered 2721' of 4 1/2" production casing. Sun cementing accomplished with 60/40 Pozmix, 2% gel, 3% cc. Maximum pressure 800# and shut in pressure at 500#.

RECEIVED
STATE CORPORATION COMMISSION
FEB 02 1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / ~~did not~~) observe this plugging.

INVOICED
DATE 2-3-84
INV. NO. 0040

Signed Richard W. Lacey
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82