

To: 1 020475  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

7-14 API NUMBER 15- 145-21,402.0000 92  
S 1/2 S 1/2 NW, SEC. 35, T. 20 S, R. 16 W/E R

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767  
Operator: Ritchie Exploration, Inc.  
Name & Address 125 N. Market, Suite 1000  
Wichita, KS 67202

2970 feet from S section line  
3960 feet from E section line  
Lease Name G. Bradley Well # 1  
County Pawnee 123.82  
Well Total Depth 3810 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 1012

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Woodman & Iannitti Drilling Company License Number 5122  
Address P.O. Box 308, Great Bend, KS 67530-0308

Company to plug at: Hour: 6 a.m. Day: 14 Month: 7 Year: 19 92

Plugging proposal received from Rich Wheeler  
(company name) Woodman-Iannitti Drilling Co. (phone) 316-792-1922

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1004-30'  
1st plug at Arbuckle with 50 sx cement, 2nd plug at 1030' with 50 sx cement,  
3rd plug at 550' with 50 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 9 a.m. Day: 14 Month: 7 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 3755' with 50 sx cement,  
2nd plug at 1030' with 50 sx cement,  
3rd plug at 550' with 50 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(if additional description is necessary, use BACK of this form.)  
Do not observe this plugging.

**INVOICED**

DATE 7-23-92  
INV. NO. 35774

Signed Glenn R Barlow  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 16 1992  
CONSERVATION DIVISION  
WICHITA, Kansas

EFFECTIVE DATE: 5-20-92

DISTRICT # 1

SSA? Yes No

State of Kansas 15.145.21402.0000

NOTICE OF INTENTION TO DRILL 145-21,402

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well.

Expected Spud Date 6 1 92 month day year

Spot 52. S2. NW. Sec 35. Twp 20 S. Rg 15. East West

OPERATOR: License # 4767 Name: Ritchie Exploration, Inc. Address: 125 N. Market #1000 City/State/Zip: Wichita, KS 67202 Contact Person: Rocky Milford Phone: (316) 267-4375

2970...2970...3820 feet from South / North Line of Section 3960...3960...3970 feet from East / West line of Section

IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License # 5122 Name: Woodman & Iannitti

County: Pawnee

Lease Name: G. Bradley Well # 1

Field Name: Pawnee Area

Is this a Prorated/Spaced Field? yes X no

Target Formation(s): Arbuckle

Nearest lease or unit boundary: 1320'

Ground Surface Elevation: 2001' Est. feet MSL

Water well within one-quarter mile: yes X no

Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 100'

Depth to bottom of usable water: 250'

Surface Pipe by Alternate: X 1 2

Length of Surface Pipe Planned to be set: 1050'

Length of Conductor pipe required: none

Projected Total Depth: 3850'

Formation at Total Depth: Arbuckle

Water Source for Drilling Operations: well farm pond X other

DWR Permit #:

Will Cores Be Taken?: yes X no

If yes, proposed zone:

Well Drilled For: Well Class: Type Equipment: X Oil Enh Rec Infield X Mud Rotary Gas Storage Pool Ext. Air Rotary OWD Disposal X Wildcat Cable Seismic # of Holes Other

If OWD: old well information as follows: Operator: Well Name: Comp. Date: Old Total Depth:

Directional, Deviated or Horizontal wellbore? yes X no

If yes, true vertical depth:

Bottom Hole Location:

Exp. 11/15/92

AFFIDAVIT

270' Alt. I Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq. It is agreed that the following minimum requirements will be met:

Pusher: Ritchie Wheeler INIT. SR. SPUD DATE: 7-8-92 LENGTH SURFACE PLANNED: 1050' of 8 1/2" RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 8 1/2" @ 10' CONDUCTOR ANHYDRITE T-100K B-1.030 ELEVATION TD 3810 FORMATION RAN PIPE @ DV TOOL ALT II DONE SX Y N 1 Arbuckle Plug @ 3755 Ft. W/ 50 SX Hug./Council @ Ft. W/ SX 2 Anhydrite Base @ 1030 Ft. W/ 50 SX 3 1/2 Base Anyh. @ 550 Ft. W/ 30 SX 1/2, 1/2 Plug @ Ft. W/ SX 4 Bottom Surface @ 40 Ft. W/ 10 SX 40' Plug @ Ft. W/ SX RAT HOLE CIRC/W/SX MOUSE HOLE W/ SX WATER WELL SX (Irr. Well Pond Hauling) TECHNICIAN G.B. DATE 7-13-92 TYPE OF CEMENT 60/40 PDS. 690 STARTING TIME 8:00 (AM/PM) DATE 7-14-92 COMPLETION TIME 9:00 (AM/PM) DATE 7-14-92 CEMENT COMPANY 1997 WICHITA CORPORATION COMMISSION RECEIVED