

5 020368

REPLUG

9-27-87

172 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 159-01.014.0001

SE SE NW, SEC. 14, T 20 S, R 8 WXX

2970 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3451

Lease Name Stahl Well # 43

Operator: American Salt Co.

County Rice

Name &

Address Box 498

Well Total Depth 1502 feet

Lyons, KS 67554

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 164

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated OWWO--Replug

Plugging Contractor Sterling Drilling Co & Halliburton License Number 5142

Address Box 129, Sterling, KS 67579

Company to plug at: Hour: 9:00am Day: 27 Month: 9 Year: 1987

Plugging proposal received from Larry Sevenker, Consultant Engineer

(company name) American Salt Company (phone)

were: Pump 25 sxs common w/3% cc through drill pipe @1470'. Pump 175 sxs

60/40 pozmix w/6% Pump 100 sxs @600' and leave set for 2 hours. Tag

top of cement. Circulate hole to cellar with 265 sxs 60/40 pozmix

w/6% gel.

Plugging Proposal Received by Gilbert J. Toman

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:30pm Day: 27 Month: 9 Year: 1987

ACTUAL PLUGGING REPORT Hole full of heavy mud. Pumped 25 sxs common cement through

drill pipe @1470'. Pulled 90' of drill pipe and pumped 175 sxs 60/40 pozmix

through drill pipe @1380'. Pulled drill pipe to 600'. Spotted 100 sxs 60/40

pozmix w/6% gel. Left set up for 2 hours. Tagged cement and pumped 175 sxs

60/40 pozmix 6% gel. Laid down 5 joints and circulated cement to cellar. Laid

down pipe and filled hole (90 sxs). Total 565 sxs cement.

Remarks: Halliburton #583435

(If additional description is necessary, use BACK of this form.)

(I did / did not) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION

Signed

SEP 30 1987

CONSERVATION DIVISION
Wichita, KansasFORM CP-2/3
Rev. 01-84